

- 1) Supply a 4 HP borewell submersible pump set for a 125 mm farm well, 415 V three phase, 60 m head and 3.5 L/s discharge.
- 2) Include 30 m of flat, three-core PVC insulated submersible cable rated 1100 V; the schedule cites IS 694:1990.
- 3) Include starter panel, protection relay and delivery column.
- 4) Conduct pump performance testing and hand over the test record.
- 5) Provide installation, warranty and operator instructions.