

Supply a 630 kVA, 11/0.433 kV oil-immersed distribution transformer with off-circuit tap changer, silica-gel breather, Buchholz relay, marshalling box and routine electrical test certificates for a campus substation.